

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21713-00-00
Spot: SESESWNE Sec/Twnshp/Rge: 2-21S-16W
2745 feet from S Section Line, 1330 feet from E Section Line
Lease Name: MERMIS Well #: 1
County: PAWNEE Total Vertical Depth: 3900 feet

Operator License No.: 34674
Op Name: H & D EXPLORATION LLC
Address: 165 WEST 1ST PO BOX 387
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3910	2140	WITH 180 SX CMT
SURF	8.625	1000		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2015 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUG BOTTOM WITH 50 SX CMT & 100# HULLS. PLUG AT 1040' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2015 2:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

PUMP 50 SX CMT WITH 200# HULLS ON BOTTOM. DISPLACED TO 3200'.
PRESSURED TO 500#. 1ST PLUG AT 1040' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG
AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3800	3801		
3636	3640		
3622	3624		
3466	3469		

KCC WICHITA
OCT 20 2015
RECEIVED
10-20-15

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

10/27/15CKM

District: 01

Signed Yang Aikuan ECKS
(TECHNICIAN)

RECEIVED
OCT 14 2015
KCC DODGE CITY