

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23851-00-00
Spot: NENENE Sec/Twnshp/Rge: 21-25S-12W
330 feet from N Section Line, 330 feet from E Section Line
Lease Name: FISHER Well #: 1
County: STAFFORD Total Vertical Depth: 4225 feet

Operator License No.: 34674
Op Name: H & D EXPLORATION LLC
Address: 165 WEST 1ST PO BOX 387
HOISINGTON, KS 67544

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 3980 | | |
| PROD | 5.5 | 4217 | 2235 | WITH 200 SX CMT |
| SURF | 8.625 | 680 | | WITH 175 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/01/2015 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 40 SX CMT WITH 200# HULLS. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL
Date/Time Plugging Completed: 10/01/2015 10:15 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

PUMPED 40 SX CMT WITH 200# HULLS. TAGGED TOC @ 3200'. 1ST PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT. CMT CIRCULATED.

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

10/27/15 CKM

District: 01

Signed Eric MacLaren

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

RECEIVED
OCT - 7 2015
KCC DODGE CITY

10-15-15 OCT 15 2015

CONSERVATION DIVISION
WICHITA, KS