

KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued May 16, 1967.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 12 1967

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Frank J. Black  
Complete Address: Box 150, McPherson, Kansas 67460  
Lease Name Hammond "A" Well No. # 2  
Location NW SW SE Sec. 9 Twp. 25 Rge. 14 (E) (W) W  
County Stafford Total Depth 3981'  
Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated:   
Plugging Contractor: Knight Casing Pulling Company  
Address: Box 405, Chase, Kansas License No. 436  
Operation Completed: Hour 9:30AM Day 10th Month June Year 1967

The Above well was plugged as follows:

264' of 8 5/8" surface pipe, cemented with 255 sacks. 3981' of 5 1/2" long string, cemented with 35 sacks. Squeezed with 150 sacks at 3925'. Top perforation 3870'. Bottom of the hole was sanded to 3850', and cemented with 5 sacks, through the dump bailer. 2480' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 260', and 5 sacks of cement and 5% Calcium Chloride was mixed in a barrel, and put on plug at rock bridge at 250', through the dump bailer, and let set over-night. Next day hole was bailed dry, and 20 sacks of cement was added to the hole. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 6/12/67  
INV. NO. 5370-W

Signed: Audie Elving  
Well Plugging Supervisor