

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 5 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Frank J. Black

Complete Address: Box 150, McPherson, Kansas

Lease Name Hammond Well No. # 1

Location NE SE SW Sec. 9 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4011'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 3:45 PM Day 4th Month May Year 1965

The Above well was plugged as follows:

408' of 8 5/8" surface pipe, cement circulated. 4011' of 5 1/2" long string,
cemented with 150 sacks. Top perferation 3999'. Bottom of the hole was
sanded to 3985', and cemented with 5 sacks. 2050' of 5 1/2" long string
was recovered from the hole. Fluid level was near the top of the hole.
Bridge plug was pushed in fluid to 280', and 10' of rock bridge on plug.
One sack of Cal-Seal was mixed in barrel and put on plug at 270', through
the dump bailer, and let set for two hours. Hole was then bailed dry, and
25 sacks of cement was added to the plug. Hole was filled with mud to 40',
and 10' of rock bridge, and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/5/65

INV. NO. 1106-4

Signed: Archie Elving
Well Plugging Supervisor