

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 16 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued May 16, 1967.

Operator's Full Name Frank J. Black

Complete Address Box 150, McPherson, Kansas 67460

Lease Name Hammond "A" Well No. # 1

Location SW NW SE Sec. 9 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 3993'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company

Address Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 10:30 A.M. Day 14th Month June Year 1967

The above well was plugged as follows:

256' of 8 5/8" surface pipe, cemented with 200 sacks. 3983' of 5 1/2" long string
cemented with 35 sacks. Plug back T.D. 3948'. Hole had been squeezed with 70
sacks of cement at 3872'. 2400' of 5 1/2" long string was recovered from the hole
Bridge plug was pushed in fluid to 250', bridge plug and rock bridge from
250' to 240'. 5 sacks of cement was mixed in a barrel, and put on plug at 240'
through the dump bailer, and let set over-night. Next day hole was bailed dry,
and 20 sacks of cement was added to the plug. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 10 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6-16-67
INV. NO. 5409-W