

15-185-30025-0000

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3  
Rev. 6-26-62

RECEIVED  
STATE CORPORATION COMMISSION

NOV 27 1967

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Well Plugging Authority,  
issued September 21, 1967

Operator's Full Name Morris Sitrin, Inc.

Complete Address: P. O. Box 318, Claflin, Kansas 67525

Lease Name Collins Well No. # 1

Location NE NE NE Sec. 9 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4247'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 1:30PM Day 17th Month October Year 1967

The Above well was plugged as follows:

262' of 8 5/8" surface pipe, cemented with 230 sacks. 4246' of 5 1/2" long string, cemented with 150 sacks. Top perforation 4088'. Bottom of the hole was sanded to 4050', and cemented with 5 sacks, through the dump bailer, with cement from 4050' to 4010'. 1667' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 250', bridge plug and rock bridge from 250' to 240'. 5 sacks of cement was mixed in a barrel, and put on plug at 240', through the dump bailer, and let set over-night. Next day hole was bailed dry, and 20 sacks of cement was added to the plug, with cement from 240' to 165'. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 11-28-67

INV. NO. 6750-W