

AP
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 8 - 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
Original issued September 21, 1967.
Renewal Issued February 2, 1968.

Operator's Full Name Morris Sitrin, Inc.

Complete Address: P. O. Box 1160, Tulsa, Oklahoma 73101

Lease Name Collins Well No. # 2

Location NW NE NE Sec. 9 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4246'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 2:15PM Day 5th Month February Year 1968

The Above well was plugged as follows:

262' of 8 5/8" surface pipe, cemented with 230 sacks. 4246' of 5 1/2" long string,
cemented with 110 sacks. Plug back T.D. 3952'. Top perferation 3864'. Bottom of
the hole was sanded to 3825', and cemented with 5 sacks, through the dump bail-
er, with cement from 3825' to 3785'. 2411' of 5 1/2" long string was recovered
from the hole. Bridge plug was pushed in fluid to 250', bridge plug and rock
bridge from 250' to 240'. 15 sacks of cement was mixed in a barrel, and put on
plug at 240', through the dump bailer, and let set over week-end. Hole was bail-
ed dry, and 10 sacks of cement was added to the plug, with cement from 240' to
165'. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 2/8/68
INV. NO. 7230-W

Signed: Audie Elving
Well Plugging Supervisor