

15-167-19454-0000

CP-3

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Leo J. Dreiling Oil Co.

Complete Address: Victoria, Kansas

Lease Name Mermis Well No. # 5

Location W/2 E/2 SE Sec. 18 Twp. 12 Rge. 15 (E) (W)

County Russell Total Depth 3340

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Company

Address: Box 304, Great Bend, Kansas License No. # 2

Operation Completed: Hour 3 PM Day 29 Month 12 Year 1962

The Above well was plugged as follows:

8 5/8" 158' Cwc.

Set bottom plug @ 2674' & dumped 4 sax cement with dump bailer. Pulled
pipe to 450', circulated hole with mud. Pulled pipe to 350' & displaced
20 sax cement thru pipe. Pulled pipe to 150' & displaced 20 sax cement
thru pipe, with mud pump. Pulled remaining pipe & displaced 10 sax
cement, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/4/63
INV. NO. 6553-W

Signed: [Signature]
Well Plugging Supervisor