

15-185-00708-0000
Form CP-3
Rev. 6-26-62

70
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply
Complete Address: P. O. Box 562, Great Bend, Kansas
Lease Name Kachelman Well No. # 1
Location NE SE SW Sec. 12 Twp. 25 Rge. 14 (E) (W) W
County Stafford Total Depth 4321
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Glen & Smith Casing Pulling
Address: 204 East Sixth, Ellinwood, Kansas License No. 396
Operation Completed: Hour 11:00AM Day 9th Month May Year 1963

The Above well was plugged as follows:

280' of 8 5/8" surface pipe, cement circulated with 225 sacks. 4321' of
5 1/2" long string, cemented with 200 sacks. Perferated from 3812' to 18'.
Plug was pushed to 3800', cemented with 5 sacks. Fluid was up in hole.
Plug was set at 225', 10' rock bridge, 5 sacks cement was mixed and
dumped on plug with dump bailer and left to set over night. Next morning
fluid bailed down O.K., 15 sacks cement was added to plug. Hole was filled
with mud to 40', 10' rock bridge, cemented with 10 sacks to base cellar.
3300' fo 5 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/13/63

INV. NO. 4061-W

Signed: Archie Elving
Well Plugging Supervisor