

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION

FEB 10 1964

CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Western Petroleum Co., Inc.Complete Address: 925 Patton Road, Great Bend, KansasLease Name Grunder Well No. # 1Location S/2 NW NE Sec. 19 Twp. 25 Rge. 14 (E) (W) WCounty Stafford Total Depth 4259Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: This hole was washed downPlugging Contractor: Forbes Casing Pulling Inc.Address: Box 221, Great Bend, Kansas License No. 49Operation Completed: Hour 12:30 PM Day 7th Month Feb. Year 1964

The Above well was plugged as follows:

253' of 8 5/8" surface pipe, cement circulated. 4235' of 5 1/2" long string,
cemented with 125 sacks. Top perforation 4149'. Bottom of hole was sanded
to 4130', and cemented with 5 sacks. Hole was squeezed. 15 sacks of Gel-Mud
and 80 sacks of cement was pumped into the surface pipe, through an 8 5/8"
swage, to a pressure of 50 lbs.

3000' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 2/11/64INV. NO. 8606-11