


STATE OF KANSAS

STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Reno County. Sec. 4 Twp. 24 Rge. 5 (#) W (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner Mull Drilling Co. Inc.  
Lease Name Miller Well No. 1  
Office Address 670 N. 4th. Natl. Bank Bldg. Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-22 1961  
Application for plugging filed 5-22 1961  
Application for plugging approved 5-22 1961  
Plugging commenced 12:00 P. M. 5-22 1961  
Plugging completed 4:00 P.M. 5-22 1961  
Reason for abandonment of well or producing formation Non productive.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3853 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with drilling mud to within 180' of top, with a plug set at this depth. 1/2 sack hulls was put on top of plug and 20 sacks cement put on top of hulls. Hole was then filled to within 40' of top and a plug was put at this depth with 1/2 sacks of hulls put on top of plug with 10 sacks cement put on top of hulls this filled hole to top of surface pipe completing plugging. Rat hole was bridged off and 2 sacks cement was used to plug same.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 2 1961 6-2-61  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Co. tools  
Address Same as above.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Joseph O. Butts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph O. Butts  
Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of May, 1961

Ethel Zimmerman  
Notary Public.

My commission expires January 28, 1965



ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc. Et Al  
Wichita, Kansas

ROTARY DRILLING COMMENCED: 5/11/61

CONTRACTOR: Mull Drilling Co., Inc.  
Wichita, Kansas

ROTARY DRILLING COMPLETED: 5/22/61

CASING RECORD: Set 197' of 8 5/8" csg.  
w/170 sx cmt.  
D & A

LOCATION: MILLER #1  
NE NE NE 4-24S-5W  
Reno County, Kansas

(Figures indicate bottom of formation -- measurements from top of Rotary Bushing.)

990'	Shale, etc.
1100'	Shale w/Lime
1730'	Lime & Shale
2650'	Sandy Lime & Shale
3393'	Lime & Shale
3608'	Mississippi
3720'	Kinderhook
3842'	Lime & Shale
3848'	Lime
3857'	Simpson - Total Depth

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUN 2 1961 6-2-61  
CONSERVATION DIVISION  
Wichita, Kansas


I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

*R. James Gear*  
R. James Gear

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 31st day of May, 1961.



*Madge N. Miller*  
Madge N. Miller, Notary Public

Commission Expires: February 24, 1964