


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Reno County, Sec. 8 Twp. 24 Rge. (E) 5 (W)  
Location as "NE/CNW/SW" or footage from lines SE SW SE  
Lease Owner Rupp-Ferguson and Monsanto  
Lease Name Ronfrager Well No. 1  
Office Address 522 Union Center, Wichita  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11-17-56 19  
Application for plugging filed 11-18-56 19  
Application for plugging approved 11-18-56 19  
Plugging commenced 11-18-56 19  
Plugging completed 11-18-56 19  
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel E. Durkee  
Producing formation Depth to top Bottom Total Depth of Well 4050 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8	245	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 225, hulls, plug, 30 sacks cement. Mud to 25', hulls, plug, cement to cellar base.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 3 1956  
CONSERVATION DIVISION  
WICHITA, KANSAS  
12-8-56

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rupp-Ferguson Oil Co.  
Address 522 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
I. W. Knox (employee of owner or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) I. W. Knox  
522 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 56

Helen Horine  
Notary Public.

My commission expires June 4, 1959

PLUGGING  
FILE SEC 8 T 24 R 5W  
BOOK PAGE 117 LINE 24

## CONTRACTOR'S WELL LOG

Rupp-Ferguson and Monsanto No. 1 Bontrager  
SE SW ~~SE~~, Sec. 8-24-5W,  
Reno County, Kansas

Commenced: 11-3-56

D & A

Completed: 11-17-56

Contractor: Rupp-Ferguson Oil Co.

Set 237' of 8 5/8" surface casing w/225 sacks.

50 surface soil  
150 sand  
230 red bed & shale  
260 shale  
440 shale & shells  
745 salt & shale  
1130 lime & shale  
1150 sand & shale  
2428 lime & shale  
2560 lime  
2812 lime & shale  
3113 lime  
3468 lime & shale  
3657 Miss.  
3828 Kinderhook  
3878 sand, lime & shale  
3904 lime & shale  
3920 Viola, Simp.  
3941 sand  
3968 sand & shale  
4002 Simp., Arb.  
4050 Arb.  
T.D.

RECORDED  
SERIALIZED  
INDEXED  
DEC 11 1956  
12-8-56

STATE OF KANSAS)  
SEDGWICK COUNTY) SS:

I, L. W. Knox, Landman for Rupp-Ferguson Oil Co., do hereby certify that the above and foregoing is a true and correct copy of the log of the No. 1 Bontrager well.

*L. W. Knox*  
L. W. Knox

Subscribed and sworn to before me this 7th day of Dec., 1956.

*Helen Horine*  
Notary Public

My Commission Expires June 4, 1959.

