

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-155-00253-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Reno County. Sec. 23 Twp. 24 Rge. 5 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW-SE-NW
Lease Owner Stearns Petroleum, Inc.
Lease Name Yoder Well No. 1
Office Address Box 313, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed April 20 19 55
Application for plugging filed April 20 19 55
Application for plugging approved April 20 19 55
Plugging commenced April 20 19 55
Plugging completed April 20 19 55
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3950 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 475 feet
Wood Plug
1/2 sack Hulls
20 sacks cement through drill pipe
Mud to 35 feet
Wood Plug
1/4 sack Hulls
10 sacks cement to surface

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stearns Petroleum, Inc.
Address Box 313, Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Stearns Petroleum, Inc.
By: [Signature] (Address)

SUBSCRIBED AND SWORN TO before me this 21 day of April, 1955

My commission expires April 5, 1958 Notary Public.

PLUGGING
FILE SEC 23 T 24 R 5W
BOOK PAGE 113 LINE 22

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1955
4-27-55
CONSERVATION DIVISION
Wichita, Kansas

YODER #1

Operator: Stearns Petroleum, Inc.
 Contractor: Stearns Petroleum, Inc.
 Commencement Date: March 8, 1955
 Completion Date: April 9, 1955
 I. P.: D. & A.

Location:
 SW SE NW
 Section 23-24S-5W
 Reno County, Kansas

Casing Record:

Set two strings of surface; ran 12 joints of 10 1/4" Casing approximately 360 ft set and cemented with 50 sacks common cement, 1 sk calcium chloride, ran 120 ft of 2" pipe cemented with 180 sacks pozmix; ran 31 joints of 8-5/8" casing approximately 663 ft set and cemented with 75 sacks pozmix and 1 sack calcium chloride.

WELL LOG

Shale & Shells	280	648
Anhydrite	648	660
Shale, Salt & Sand	660	785
Shale & Shells	785	1250
Shale & Sand	1250	1315
Shale & Lime	1315	1770
Red Bed & Shale	1770	1800
Shale, Sandy Lime	1800	1876
Shale & Lime	1876	2300
Lime	2300	2350
Lime & Shale	2350	2565
Sand	2565	2630
Sand & Brown Lime	2630	2638
Shale	2638	2670
Lime & Shale	2670	2805
Lime	2805	3080
Shale & Lime	3080	3387
Lime	3387	3405
Lime & Chert	3405	3590
Lime & Shale	3590	3751
Lime	3751	3837
Sand	3837	3858
Shale	3858	3880
Lime & Shale	3880	3950
Total Depth	3950	

STATE OF KANSAS)
) SS:
 COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

[Signature]

SUBSCRIBED AND SWORN to before me, a Notary Public, this 28th day of April, 1955.

NOTARY PUBLIC
 APR 28 1955
 COUNTY OF RUSSELL, KANSAS

Betty Lou Miller

My Commission Expires: April 5, 1958.

PLUGGING
 FILE SEC 23-24 R. 5W
 BOOK PAGE 113 LINE 22