


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Reno County, Sec. 24 Twp. 24 S Rge. 5 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines C SW/4 NE/4  
Lease Owner Excalibur Production Co., Inc.

Lease Name Petershein Well No. 1  
Office Address P. O. Box #231, McPherson, Kans. 67460

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed Sept. 2 1971

Application for plugging approved Sept. 3 1971

Plugging commenced Sept. 27 1971

Plugging completed ~~Sept. 27~~ Oct. 2 1971

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set rock bridge at 2500' and dumped 5 sacks of cement. Shot pipe off at 2416.25'. Pulled pipe and mudded hole to 210'. Set rock bridge from 210' to 200' and finished filling hole with ready mix cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 7 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self  
Address Hutchinson, Kans.

10-7-71


STATE OF Kans., COUNTY OF Reno, ss.  
Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self  
R. R. #4, Hutchinson, Kans. 67501  
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of October, 1971

My commission expires October 18, 1973

Notary Public.



Handwritten signature of Notary Public.



15-155-20170-00-00

# Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON, KANSAS 67460

February 5, 1971

COMPANY: EXCALIBUR PRODUCTION CO., INC.  
 CONTRACTOR: BLACKSTONE DRILLING, INC.  
 FARM: PETERSHEIM #1  
 LOCATION: C SW/4 NE/4, Sec. 24-24S-3W  
 RENO COUNTY, KANSAS  
 COMMENCED: January 28, 1971  
 COMPLETED: Feb. 5, 1971  
 ELEVATION: 1484 K. B.

0	to	10	Dirt & Clay
10	to	70	Sand
70	to	231	Shale
231	to	478	Shale & Lime
478	to	595	Salt
595	to	605	Shale
605	to	1030	Shale & Lime
1030	to	1725	Shale
1725	to	2095	Shale & Lime
2095	to	2295	Lime
2295	to	2627	Lime & Shale
2627	to	2756	Lansing
2756	to	3090	Lime
3090	to	3338	Lime & Shale
3338	to	3528	Mississippi
3528	to	3580	Lime & Shale
3580	to	3666	Shale
3666	to	3694	Hunton
3694	to	3768	Shale
3768	to	3791	Viola
3791	to	3799	Simpson
		3799	T. D.

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 3 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas

9-3-71

JN

Cut 15 1/4 in. hole to 231 ft. and run 246 ft. of 1 3/8 in. surface pipe, cemented with 200 sacks at 231 ft. Plug down at 3:30 P. M., January 27, 1971. Run 607 ft. of 2 5/8 in. pipe, cemented with 100 sacks at 605 ft. Plug down at 1:00 P. M., January 28, 1971. Cut 7 7/8 in. hole to 3799 ft. and run 3450 ft. of 5 1/2 in. pipe, cemented with 150 sacks at 3445 ft. Plug down at 8:30 A. M., February 5, 1971.

TOPS: LANHING - 2627'      MISSISSIPPI - 3338'      KINDERHOOK - 3533'      HUNTON - 3666'  
 VIOLA - 3768'      SIMPSON - 3791'

Measurements taken from K. B.

### CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your PETERSHEIM #1, located on the C SW/4 NE/4, Sec. 24-24S-3W, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Plouffe, President



Johnnie L. Schmidt - Notary Public

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 8th day of February, 1971.

My Commission Expires: June 27, 1973.