


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Reno County. Sec 24 Twp. 94 Rge. 5 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NE NE SW  
Lease Owner W. R. ALLAM JR.  
Lease Name Kaufman Well No. 1  
Office Address 6 Eastwood Hutchinson, KS.  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plat

Date Well completed July 30 1979  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 9-5- 1980  
Plugging completed 9-9 1980  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well B. Allen Town  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3471  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5x9		2315.80

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Push plug to bottom and sand back to 3375' Put in five sets of cement 2" diameter hole to 930 feet and made a 15' sand body and filled with sand mix to dry top


RECEIVED  
STATE CORPORATION COMMISSION  
SEP 25 1980  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wood Hunt Co.

STATE OF Kansas COUNTY OF Reno, ss.  
Mark Hunt (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Mark Hunt  
8 East 3rd Hutchinson, KS 67501  
(Address)



SUBSCRIBED AND SWORN TO before me this 17th day of September, 1980

Michael Olivier  
Notary Public.

My commission expires 12-5-82



# Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250  
McPHERSON, KANSAS 67460

July 31, 1979

COMPANY: HAVEN OIL & GAS COMPANY  
 CONTRACTOR: BLACKSTONE DRILLING, INC.  
 FARM: KAUFFMAN #1  
 LOCATION: NE NE SW Section 24-24-5W,  
 Reno County, Kansas  
 COMMENCED: July 24, 1979  
 COMPLETED: July 30, 1979  
 ELEVATION:

0	to	130	Clay & Sand
130	to	485	Shale
485	to	585	Salt
585	to	648	Shale & Lime
648	to	840	Lime
840	to	1115	Lime & Shale
1115	to	1690	Shale & Lime
1690	to	1925	Lime & Shale
1925	to	2645	Shale & Lime
2645	to	2835	Lime
2835	to	3035	Lime & Shale
3035	to	3170	Shale & Lime
3170	to	3253	Lime
3253	to	3320	Lime & Shale
3320	to	3430	Mississippi
		3430	T. D.

9-19-80  
 RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 19 1979  
 CONSERVATION DIVISION  
 Wichita, Kansas

Cut 17 1/2" hole to 226' and run 228' of 13" surface pipe, cemented at 226' with 250 sacks of cement. Plug down at 1:45 P. M., July 24, 1979. Run 626' of 8 5/8" casing, cemented with 150 sacks of cement at 624'. Plug at 209'. Plug down at 1:45 P. M., July 25, 1979. Cut 7 7/8" hole to 3430'. Run 3431' of 5 1/2" casing, cemented at 3429' with 150 sacks of cement 1 foot off bottom at 3429'. Plug down at 8:20 A. M., July 30, 1979.

TOPS: MISSISSIPPI - 3320'

Measurements taken from K. B.

### CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Kauffman #1, located on the NE NE SW Section 24-24-5, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.

*P. E. Plouffe*  
 P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 31st day of July, 1979.

*Johnnie L. Schmidt*  
 Johnnie L. Schmidt - Notary Public

JOHNNIE L. SCHMIDT  
 McPherson County, Kansas  
 Exp. App. Em. June 23, 1981