

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 9-23-69

LEASE NAME Kincaid

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4,950 Ft. from S Section Line

2,310 Ft. from E Section Line

SEC. 21 TWP. 24 RGE. 4W (E) or (W)

COUNTY Reno

LEASE OPERATOR FECO

ADDRESS 1134 Armstrong, Wichita, Ks.

PHONE # 816, 788-6282 OPERATORS LICENSE NO. 9059

Date Well Completed 9-23-69

Character of Well good

Plugging Commenced 10-21-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-23-91

The plugging proposal was approved on 10-21-91 (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Miss Depth to Top 3367 Bottom 3374 T.D. 3374

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

11-13-91
NOV 13 1991

Formation	Content	From	To	Size	Put in	Pulled out
Miss	Water	0	332	8 5/8	333	None
		0	3367	5 1/2	3367	2,090

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded back to 3305 Dumped 5 sacks cement with baller, Shot casing off at 2,090 Pulled casing to 565' foot Pumped 35 sacks bridge, Pulled casing to 401 ft. circulated cement to top. Pulled casing on out filled surface pipe with cement 4' foot below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lyons Well Service License No. 30375

Address 1103 S St. John Lyons, Kansas 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rick Gagnebin

STATE OF Kansas COUNTY OF Reno, ss.


Rick Gagnebin (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Rick Gagnebin

(Address) Hatchinson, Ks 67501

12th day of November, 19 91

Darleen Hagler
Notary Public



My Commission Expires: March 29 1993