


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Reno County. Sec. 14 Twp. 24 Rge. 8 (E) (W)
Location as "NE/CNW%SW%" or footage from lines SE SE SW
Lease Owner Shawver-Armour, Inc.
Lease Name McNeil Well No. 1
Office Address 817 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 16, 19 60
Application for plugging filed September 16, 19 60
Application for plugging approved September 16, 19 60
Plugging commenced September 16, 19 60
Plugging completed September 16, 19 60
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	water	-0-	197'	8 5/8"	197'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 180'

#1 Plug Howco Plug 1/4 sx Hulls 15 sx cement

Heavy mud to 35'

#2 Plug howco Plug 1/4 sx Hulls 10 sx cement

Bridged rat hole 5' 2 sx. cement

9-27-60
SEP 27 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shawver-Armour, Inc.
Address 817 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James M. Armour

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

James M. Armour817 Central Bldg., Wichita, KansasSUBSCRIBED AND SWORN TO before me this 22nd day of September, 19 60

My commission expires

Dec. 29, 1963Marjorie Hall

Notary Public.

D R I L L E R ' S L O G

FARM NAME: McNeil # 1 LOCATION: SE SE SW
 Sec. 14-24-8W
 CONTRACTOR: SHAWVER-ARMOUR, INC. Reno County, Kansas
 OWNER: SHAWVER-ARMOUR, INC. ELEVATION: 1631 K. B.
 COMMENCED: September 6, 1960 COMPLETED: September 16, 1960
 CASING RECORD: 197' 8 5/8" w/150 sx. cement 4% CC

FORMATION:TOPS:

Sand & Clay 85
 Red Bed 420
 Grey Shale 1025
 Shale & Lime 1640
 Lime & Shale 2000
 Shale & Lime 2160
 Lime & Shale 3204
 Kansas City Lime 3590
 Lime & Shale 3726
 Mississippian Lime & Chert 3780

Kansas City 3216 -1585
 Mississippian 3769 -2138

Total Depth 3780

RECEIVED
 STATE COMMISSION
 SEP 27 1960

CONSERVATION DIVISION
 WICHITA

9-27-60

STATE OF KANSAS)
 SEDGWICK COUNTY) ss

I, James M. Armour, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER-ARMOUR, INC.

BY

James M. Armour

Subscribed and sworn to before me this
 22nd day of September, 1960

My commission expires Dec. 29, 1963

Marjorie Hall, Notary Public