


R

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Reno County. Sec. 13 Twp. 24 Rge. 8 (E)W (W)  
Location as "NE/CNW/SW" or footage from lines SE SE  
Lease Owner West Supply Co., Inc.  
Lease Name Love #6 Well No.  
Office Address Chase, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19.  
Application for plugging filed 19.  
Application for plugging approved 19.  
Plugging commenced 11-12-59 19.  
Plugging completed 11-19-59 19.  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19.  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation Depth to top Bottom Total Depth of Well 3522 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	112'	none
				5-1/2"	3518'	2966'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 24 1959

CONSERVATION DIVISION  
Wichita, Kansas  
11-24-59

Checked the hole to 3522' and found it open.  
Filled w/sand to 3500' and dumped 5 sacks of  
cement with dump bailer. Pulled 5 1/2" casing.  
Cleared hole and tried but could not bail  
hole down. Mudded the hole to 180', set rock  
bridge to 180' and dumped 4 sacks of cement  
with bailer. Left set overnight. Bailed  
hole to 180' and dumped 11 more sacks of  
cement. Mudded the hole to 110', set rock  
bridge to 100' and dumped 10 sacks of cement.  
Mudded the hole to 15', set rock bridge and  
ran 5 sacks of cement to base of cellar.

Name of Plugging Contractor Knight Casing Pulling Co.  
Address Chase, Ks.

STATE OF KANSAS, COUNTY OF RICE, ss.  
I, Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
Chase, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of November, 19 59

Thomas V. Duggan  
Notary Public.

My commission expires 9-27-62

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
Wichita, Kansas

COPY


Company - NAT'L PET. RES. CORP., et al  
Farm - Love No. 6

SEC. 13 T. 24 R. 8W  
SE/c SE

Total Depth. 3522  
Comin. 10-11-49 Comp. 10-25-49  
Shot or Treated.  
Contractor. Donald T. Ingling  
Issued. 12-31-49

County. Reno

KANSAS



Elevation. \_\_\_\_\_

Production. Est. 100 Bbls.

Figures Indicate Bottom of Formations.

Surface	40
Sand & shale	80
Red bed & rock	110
Red rock & shale	640
Shale & shells	1120
Lime	1260
Shale	1360
Lime	1600
Lime & shale	2020
Shale & lime shells	2130
Shale & lime	2415
Shale & lime shells	2530
Shale & lime	2695
Lime	2950
Shale & lime	2970
Lime	3075
Shale	3100
Sand & shale	3140
Lime	3460
Total Depth	3522

RECEIVED  
STATE CORPORATION COMMISSION

NOV 6 1959

CONSERVATION DIVISION  
Wichita, Kansas

11-6-59