

LEASE NAME Perkins

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
 Ft. from S Section Line
 Ft. from E Section Line

LEASE OPERATOR Smokey Valley Resources

SEC. 13 TWP. 24S RGE. 8W (E) or (W)

ADDRESS Rt 3, Box 63 Lyons, KS 67554

COUNTY Reno

PHONE (316) 257-5529 OPERATORS LICENSE NO. 4424

Date Well Completed

Character of Well Oil

Plugging Commenced 12-13-96

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Plugging Completed 12-14-96

The plugging proposal was approved on (date)
by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3825'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	206'	none
				4 1/2	3825'	2407'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from feet to feet each side. Sanded off bottom to 3460' & 4 sks cement. Shot well at 2407', casing came free. Pulled casing to 1200', mixed 35 sks cement. Pulled casing to 700', mixed 200# hulls & 35 sks cement. Pulled casing to 250' & circulated cement to surface with 70 sks. Pulled rest of casing & topped off with 5 sks cement. Plugging complete. 60/40 poz 4% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Smokey Valley Resources

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 31st day of December, 1996

Jane Sterberg
Notary Public

My Commission Expires:



1-6-97

RECEIVED
KANSAS CORP. COM.
NOV 14 1996