

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER #15-155-21,244-00-00

#2

LEASE NAME Trembley

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1-22

330 Ft. from S Section Line

3080 Ft. from E Section Line

LEASE OPERATOR Stelbar Oil Corp., Inc./Grand Mesa Oper. Co.

SEC. 22 TWP. 24 SRGE. 8 (E) or (W)

ADDRESS 155 N. Market, Suite 500, Wichita, Ks. 67202

COUNTY Reno County, Kansas

PHONE# (316)264-8378 OPERATORS LICENSE NO. 6044 & 9855

Date Well Completed 3-8-93

Character of Well D & A

Plugging Commenced 3-8-93 @ 4:45 pm

(Oil, Gas, (D&A), SWD, Input, Water Supply Well)

Plugging Completed 3-9-93 @ 7:30 am

The plugging proposal was approved on March 4th, 1993 (date)

by Don Thompson (KCC District Agent's Name).

Is AC0-1 filled? Yes If not, is well log attached? Yes

Producing Formation Simpson Depth to Top _____ Bottom _____ T.D. 4110'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface Soil & Sand		0'	95'			
Red Bed		95'	210'	8 5/8"	209'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Filled hole with Heavy mud with 35 sacks at 1200' with heavy mud to 700' with 35 sacks with Heavy mud to 270' with 35 sacks, heavy mud to 60' with 25 sacks to surface, 10 sacks in rathole with 10 sacks in mousehole, used 60x40 pozmix with 4% gel, all plugs set through open ended drill pipe, Don Thompson State Plugger was not present, Vaughn Thompson was Sterling Drilling Co. witness (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address PO Box 129, Sterling, Kansas 67579-0129

STATE OF Kansas COUNTY OF Reno, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
Sterling Drilling Company

(Address) PO Box 129, Sterling, Ks. 67579-0129

SUBSCRIBED AND SWORN TO before me this 9th day of March 1993

Cheryl R. Davis
Notary Public

My Commission Expires: _____



RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1993
3-19-93
REGISTRATION DIVISION
Wichita, Kansas
Form CP-4
Revised 07-87

Job Completed at 7:30 a.m. on 3-9-93 by Allied Cementing Co. Ticket # 1303.

3/9/93 7:30 AM
Allied Cementing Co.
Ticket # 1303