


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Reno County. Sec. 21 Twp. 24 Rge. 8 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines _____
SW NW SE

Lease Owner Hinkle Oil Company
Lease Name Foster Well No. 1
Office Address 1016 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed November 12 1976
Application for plugging filed November 12 1976
Application for plugging approved November 12 1976
Plugging commenced November 12 1976
Plugging completed November 12 1976
Reason for abandonment of well or producing formation _____
Dry Hole

If a producing well is abandoned, date of last production _____
19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3620
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug at 500' w/40 sacks 50/50 Pozmix, 2% Gel.

Middle plug at 240' w/25 sacks 50/50 Pozmix, 2% Gel.

Top plug at 40' w/1/2 sack hulls & 10 sacks 50/50 Pozmix, 2% Gel.

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1976

11-17-76
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

STATE OF KANSAS COUNTY OF BARTON, ss.
Wayne Dobbs (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Wayne Dobbs
Box 823, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 1976

Rosemary M. Hogue
Notary Public.

My commission expires April 11, 1978

DRILLERS' WELL LOG

DATE COMMENCED: November 2, 1976
 DATE COMPLETED: November 12, 1976

Hinkle Oil Company
 FOSTER # 1
 SW NW SE
 Sec 21-T24-R8
 Reno County, Kansas

ELEVATION: 1619 K.B.

0 - 50' Sand
 50 - 249' Red Bed
 249 - 1480' Shale
 1480 - 2480' Lime and Shale
 2480 - 2547' Lime
 2547 - 2594' Shale and Sand
 2594 - 3490' Lime
 3490 - 3610' Lime and Shale
 3610 - 3620' Shale
 3620' RTD

FORMATION TOPS

Her-Kri	1300
Winfield	1350
Towanda	1420
Base Florence Flint	1560
Red Eagle	1915
Penn	2080
Stotler	2260
Tarkio	2315
Howard	2480
Severy	2547
Topeka	2594
Lensing	3124
Base K.C.	3490
Kinderhook	3610
RTD	3620

SURFACE PIPE:

Set new, 20# 8 5/8" pipe @
 249' w/225 sacks Common,
 2% Gel, 2% cc.

AFFIDAVIT

NOV 17 1976
 11-17-76

STATE OF KANSAS)
 COUNTY OF BARTON) ss.

Wayne Dobbs, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Wayne Dobbs

Subscribed and sworn to before me this 16th day of November, 1976.

Harold M. Hague
 Notary Public

My Commission Expires: April 11, 1978