

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

15-185-00707-6000

Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 3/09/57 (Identifier number of this Well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Knighton Oil Company, Inc. KCC LICENSE # 5010
(owner/company name) (operator's)

ADDRESS 710 Petroleum Building CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 264-7918

LEASE English WELL# 1 SEC. 29 T. 25S R. 14 (RRR/West)

- SW - NE - SE SPOT LOCATION/QQQQ COUNTY Stafford

1650 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL X GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8" SET AT 287' CEMENTED WITH 275 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 4299' CEMENTED WITH 225 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3905-3915, 3944-3956

ELEVATION 2004 K.B. T.D. 4300 PBSD 4299 ANHYDRITE DEPTH 905
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING According to rules and regulations of Kansas Corporation Commission.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No

If not explain why? Prior to ACO-1 Form.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

William Astle PHONE# (316) 549-6436

ADDRESS Route #1, Box 30 City/State St. John, Kansas 67576

PLUGGING CONTRACTOR Pratt Well Service, Inc. KCC LICENSE # 5893
(company name) (contractor's)

ADDRESS P. O. Box 847, Pratt, Kansas 67124 PHONE # (316) 672-2531

PROPOSED DATE AND HOUR OF PLUGGING (if known?) March 18, 1996 9:00 A.M.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3/13/96 AUTHORIZED OPERATOR/AGENT: Earl M. Knighton, Jr.

(signature)
Earl M. Knighton, Jr.

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: February 23, 1957

Contractors: Quaker Drilling Co., Inc.

Completed: March 9, 1957

H. Lois English No. 1
SW NE SE Sec. 29-25S-14W
Stafford County, Kansas

Elevation: 2004 KB

Casing Records:

Set 8 5/8 inch casing at 287 feet with 275 sacks cement
Set 5 1/2 inch casing at 4299 feet with 225 sacks cement

(Figures Indicate the Bottom of the Formations)

FORMATION	DEPTH	FORMATION TOPS	
Sand	233	Anhydrite	905
Shale and Shells	405	Heebner	3591 -1587
Red Bed	905	Brown Lime	3742 -1738
Anhydrite	930	Lansing	3764 -1760
Shale and Shells	1750	Base of Kansas City	4060 -2056
Shale and Lime	4175	Conglomerage	4180 -2176
Shale and Cherty Lime	4220	Mississippian	4196 -2192
Lime	4225	Kinderhook	4210 -2206
Lime and Chert	4300	Viola	4268 -2264
		Rotary Total Depth	4300 -2296

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SW NE SE of Section 29, Township 25 South, Range 14 West, Stafford County, Kansas.

QUAKER DRILLING CO., INC.

By: _____
Thomas M. McCaul, President

SUBSCRIBED AND SWORN to before me a Notary Public this 11th day of March, 1957.

Virginia Mundell, Notary Public

MY COMMISSION EXPIRES:
August 10, 1957.