



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission  
CONSERVATION DIVISION  
(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JAN 3 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Leo J. Dreiling of Leo J. Dreiling Oil Co. has this  
date requested permission to plug the following described well:

Mr. Leo J. Dreiling guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Co.

Complete Address: Victoria, Kansas

Lease Name: Mermis Well No. # 5

Location: W/2 E/2 SE Sec. 18 Twp. 12 Rge. 15 (E) (W)

County Russell Total Depth 3340 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Russell Haberecht was instructed to plug the well as follows:

8 5/8" 158' CWC.

Set bottom plug @ 2674' & dumped 4 sax cement with dump

bailer. Pulled pipe to 450', circulated hole with mud.

Pulled pipe to 350' & displaced 20 sax cement thru pipe.

Pulled pipe to 150' & displaced 20 sax cement thru pipe.

Pulled pipe & displaced 10 sax cement, cementing to base  
of cellar.

Very truly yours,

Don. Truesdell  
Conservation Division Agent