

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAY 13 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Buck Smith of Glen & Smith Casing Co. has this

date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Santa Fe Pipe & supply

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name: Kachelman Well No. # 1

Location: NE SE SW Sec. 12 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4321 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

280' of 8 5/8" surface pipe, cement circulated with 225
sacks. 4321' of 5 1/2" long string, cemented with 200 sacks.
Perforated 3812' to 18'. Plug pushed to 3800', cemented
with 5 sacks. Fill hole with mud to 225', 10' rock bridge,
cement with 20 sacks. Fill hole with mud to 40', 10' rock
bridge, cement with 10 sacks to base cellar.

Very truly yours,

Audie Elving
 Conservation Division Agent