

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. F. L. Copeland of Western Petroleum Co. Inc. has this date requested permission to plug the following described well:

Mr. Copeland guarantees payment of the plugging fee.

Operator's full Name: Western Petroleum Co. Inc.

Complete Address: 925 Patton Road, Great Bend, Kansas

Lease Name: Boylan Well No. # 1

Location: C NE SW Sec. 19 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4350 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Copeland was instructed to plug the well as follows:

308' of 8 5/8" surface pipe, cemented with 300 sacks.
Fill hole with mud to 300', 1st cementing plug, 1/2 sack
hulls, cement with 20 sacks. Fill hole with mud to 40',
2nd cementing plug, 1/2 sack hulls, cement with 10 sacks
to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent