

SIDE TMD

Operator Name Kenneth S. White

Lease Name Bass Well # 1

Sec. 11 Twp. 29 Rgs. 14 East West

County Pratt

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken Yes No
(Attach Additional Sheets.)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
(Submit Copy.)

List All E.Logs Run:
Compensated Density/Neutron
Dual Induction

Name	Top	Datum
Heebner	2815	-1817
Douglas	3877	-1879
Brown Lime	3985	-1987
Lansing	4001	-2003
Hertha	4334	-2336
Base KC	4371	-2373
Marmaton	4384	-2386
Viola	4500	-2502
Simp Shale	4563	-2563
Simpson Sand	4573	-2575
Arbuckle	4676	-2678

CASING RECORD New Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In. O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4"	8 5/8"	28	307	60/40Poz	200	2% gel 3% C.C.

ADDITIONAL CEMENTING/SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth

TUBING RECORD Size Set At Packer At Liner Run Yes No

Date of First, Resumed Production, (SWD or Inj.) Producing Method Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity

Disposition of Gas: Vented Sold Used on Lease (if vented, submit ACO-18.)

METHOD OF COMPLETION

Open Hole Perf. Dually Comp. Commingled Other (Specify)

Production Interval

ORIGINAL

Attached to and Made a Part of
ACO-1 form for
KENNETH S. WHITE
#1 BASS
SE NE SW Section 11-29S-14W
Pratt County, Kansas

15-151-22142

DST #1 4550' - 4570' (Simpson)

30-45-30-30

1st Open: Weak 1/2" Blow

2nd Open: No blow, flushed tool 22 minutes into final flow

Rec: 20' of Drilling Mud with oil scum on top of tool

FP: 25# - 26#, 20# - 30# IHP: 2252#

ISIP: 32# FSIP: 51# FHP: 2288#

DST #2 4558' - 4574' (Simpson)

15-30-15-30

1st Open: Very Weak Surface Blow

2nd Open: No Blow

Rec: 5' Drilling Mud with a few oil specks

FP: 27# - 31#, 33# - 35# IHP: 2275#

ISIP: 979# FSIP: 830# FHP: 2258#

DST #2 4558' - 4579' (Simpson)

30-60-60-60

1st Open: Weak blow 1/4" to 1/2"

2nd Open: Weak 1/4" blow, 1/4" decreasing, dead in 43 minutes

Rec: 60' Drilling Mud with a few specks of oil

FP: 23# - 33#, 37# - 50# IHP: 2336#

ISIP: 1057# FSIP: 940# FHP: 2265#

RECEIVED
KANSAS CORP COIM
1998 APR -3 P 12:19

ALLIED CEMENTING CO., INC.

0103

REMIT TO P.O. BOX 31 RUSSELL, KANSAS 67665. SERVICE POINT: med. lodge, ks

ORIGINAL

DATE <u>3-12-96</u>	SEC. <u>11</u>	TWP. <u>19S</u>	RANGE <u>14W</u>	SECTION <u>10</u>	CALLER'S NAME <u>10:00 A.M.</u>	ON LOCATION <u>12:45 P.M.</u>	JOB START <u>2:00 P.M.</u>	JOB FINISH <u>3:30 P.M.</u>
LEASE <u>Bas</u>	WELL # <u>1</u>	LOCATION <u>COATS 1/2 N 1/2 E</u>			COUNTY <u>Pratt</u>	STATE <u>Ks.</u>		

OLD OR NEW (Circle one)

CONTRACTOR Pickrell, Drlg. OWNER Kenneth S. White

TYPE OF JOB Rotary Plug CEMENT

HOLE SIZE 7 7/8 T.D. 4699' AMOUNT ORDERED 125 sxs. 60/40/6% Gel

CASING SIZE 8 5/8 DEPTH 310'

TUBING SIZE _____ DEPTH _____

DRILL PIPE 4 1/2 x hole DEPTH 800'

TOOL _____ DEPTH _____

PRES. MAX 150 MINIMUM 50 COMMON 75 @ 6.10 = 457.50

MEAS. LINE _____ SHOE JOINT _____ POZ MIX 50 @ 3.75 = 187.50

CEMENT LEFT IN CSG _____ GEL 7 @ 9.50 = 66.50

PERFS. _____ CHLORIDE _____ @ _____ = _____

EQUIPMENT _____ @ _____ = _____

PUMP TRUCK CEMENTER Arny D. HANDLING 125 @ 1.05 = 131.25

265 HELPER Carl B. MILEAGE 125 x 15 = 1875.00

BULK TRUCK # 227 DRIVER John K. TOTAL \$ 892.75

BULK TRUCK # _____ DRIVER _____

REMARKS: _____ SERVICE _____

800' w/ 50 sxs. DEPTH OF JOB 800'

340' w/ 50 sxs. PUMP TRUCK CHARGE 443.00

40' w/ 10 sxs. EXTRA FOOTAGE @ _____ = _____

Rathole w/ 15 sxs. MILEAGE 15 @ 2.35 = 35.25

Cemented w/ 125 sxs. 60/40/6% Gel PLUG Dry Hole 8 5/8" @ 23.00 = 23.00

TOTAL \$ 503.25

CHARGE TO: Kenneth S. White

STREET 200 EAST 1ST # 405 FLOAT EQUIPMENT _____

CITY WICHITA STATE KANSAS ZIP 67202

TAX _____

TOTAL CHARGE \$ 1396.00

DISCOUNT \$ 279.20 IF PAID IN 30 DAYS

Net \$ 1116.80

TOTAL _____

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment,

and furnish cementer and helper to assist owner or

contractor to do work as is listed. The above work was

done to satisfaction and supervision of owner agent or

contractor. I have read & understand the "TERMS AND

CONDITIONS" listed on the reverse side.

SIGNATURE X [Signature]