

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford County, Sec. 12 Twp. 25S Rge. 14 (W)

Location as "NE/CNW/SW" or footage from lines C- SW NE SW
Lease Owner Cooperative Refinery Association
Lease Name Kachelman "A" Well No. 2
Office Address Box 765 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed June 19 19 57
Application for plugging filed June 19 (verbal permission obtained) 19 57
Application for plugging approved " " " 19
Plugging commenced June 19 19 57
Plugging completed June 19 19 57
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Brundage
Producing formation Depth to top Bottom Total Depth of Well 4165 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	280	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from T.D. 4165' to within 50' of top.
Dumped 1/3 sx. hulls. Set 8 5/8" plug at 250'. Cemented with
20 sx. cement thru drill pipe. Top plug at 25'. Dumped 5 sx.
cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C.R.A. Rig #5
Address Box 765, Great Bend, Ks.

STATE OF KANSAS, COUNTY OF BARTON, ss.
John H. Nation (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Nation
Box 765 Great Bend, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of June, 19 57

My commission expires September 24, 1960

Yvonne Adams Notary Public.

PLUGGING
FILE SEC 12 T 25 R 14 W
BOOK PAGE 21 LI 43

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1957 6-20-57

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

Kachelman "A" #2

Loc: C-SW NE SW
 Sec: 12-25S-14W
 Stafford County, Kansas
 Operator: Cooperative Refinery Ass'n.
 Contractor: Company Rig #5

Elevation: 1968'
 Casing: 8 5/8" at 280' w/ 225 sx.

Comm: 6-5-57 Comp: 6-19-57
 Total Depth: 4165'

<u>From</u>	<u>To</u>	<u>Formation</u>
0	280	Clay, sand, shale, shells
280	1350	Red bed, shale, shells
1350	1600	Shale, lime, shells
1600	2580	Lime and shale
2580	2690	Lime, shells, shale
2690	3310	Shale and lime
3310	3370	Shale
3370	3862	Shale and lime
3862	3865	Lime
3865	3925	Lime and shale
3925	3975	Lime
3975	4040	Lime and shale
4040	4065	Lime and chert
4065	4105	Shale
4105	4165	Shale, lime, chert
4165		R.T.D.

(STATE OF KANSAS)

(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the Kachelman "A" #2 well, located C SW NE SW of Section 12-25S-14W, Stafford County, Kansas

Jack R. Jones

Subscribed and sworn to before me this 20 day of June 1957.

Yvonne Adams

My commission expires: September 24, 1960

RECEIVED
 STATE CORPORATION COMMISSION

JUN 21 1957

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 WELL SEC. 12 T. 25 R. 14W
 BOOK PAGE 21 LINE 43