

RECEIVED
STATE CORPORATION COMMISSION Form CP-4
Rev. 12-15-80

AUG 30 1982

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 12 TWP. 25 S RGE. 14 W E/W
Location as in quarters or footage from lines:
SW - NE - NW

Lease Owner Petroleum, Inc.
Lease Name Seevers Well No. 11-2
Office Address 300 W. Douglas O- Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): injection
Date Well Completed 10-59 X
Application for plugging filed 6-28-82
Plugging commenced 8-6-82
Plugging completed 8-20-82 X
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Metz

Producing formation _____ Depth to top _____ bottom _____ T.D. 4,320

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	270	None
				4 1/2	4218	

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged back at 4,033
Top perf at 3,765 - 3,767.
Sun Cementing Company pumped in 25 sacks 50-50 POZ
Stop plug at 3,439
Ripped pipe at 2,800 and 2,600
Sun pumped in 10 sacks jell - 25 sacks 50-50- POZ
Sun Cementing pumped in 4 hull - 15 jell - 1 hull
125 sacks 50-50 POZ - 4% Jell - 3% C. C.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Clarke Corporation


STATE OF Kansas COUNTY OF Barber, ss.
Elmer R. Morquardt (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed, and that the same are true and correct. So help me God.

(Signature) Elmer R. Morquardt
Medford, Mo.
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of Aug., 1982

Jessie Hamilton
Notary Public.

Commission expires: April 4, 1986.



WELL LOG

COMPANY **PETROLEUM, INCORPORATED**

SEC. **12** T. **25S** R. **14W**

FARM **BOWKER "B" NO. 2**

LOC. **SW, NE, NW**


Levers Unit 11-2

TOTAL DEPTH **4320'**

COUNTY **STAFFORD CO., KANSAS**

COMM. **September 28, 1959** COMP. **October 11, 1959**

CONTRACTOR **G ARVEY DRILLING COMPANY**



CASING **8 5/8" @ 270' W/200 sax.**
4 1/2" @ 4218' W/350 sax.

ELEVATION **1957' DF**

PRODUCTION **Viola**

FIGURES INDICATE BOTTOM OF FORMATIONS

159	Sand & clay
270	Clay & shale
855	Red bed & shale
885	Anhydrite
1530	Shale & shells
1905	Shale & lime
2247	Lime
2360	Lime & shale
3290	Shale & lime
3537	Lime & shale
3633	Lime & sand
3722	Lime & shale
3950	Lime
3979	Lime & shale
4034	Lime
4050	Chert
4052	Cherty lime
4100	Shale
4150	Cherty lime
4250	Lime & chert
4311	Shale
4320	Arbuckle
4320	T. D.

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1959
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #2 BOWKER "B" well.

Verne A. Morris

Subscribed and sworn to before me this 20th day of October 19 59

My Commission Expires: April 14, 1963

Arthur J. Wiles
NOTARY PUBLIC