


STATE OF KANSAS
- STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

STAFFORD County. Sec. 12 Twp. 25S Rge. 14W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW NW SE
Lease Owner K & E and MCKNAB
Lease Name COPELAND Well No. 1
Office Address 719 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed May 15th, 1959 19
Application for plugging filed May 15th, 1959 19
Application for plugging approved May 15th, 1959 19
Plugging commenced May 15th, 1959 19
Plugging completed May 15th, 1959 19
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3975 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
					8-5/8 ^{BB}	set @ 285'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill with heavy mud to 240' set plug with
20 sx cement thru drill pipe. Fill with
heavy mud to 35' set solid bridge with 10 sx
cement to base of cellar. Job complete
5-15-59.

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott
Dale Silcott, of K & E DRILLING, INC.
719 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May, 19 59

My commission expires August 11th, 1962.

Patricia M. Edwards, Notary Public.

PLUGGING
FILE SEC 12 T. 25 R. 14
BOOK PAGE 39 LINE 26

DRILLER'S WELL LOG

OPERATOR: K & E & MCKNAB
719 Union Center
Wichita, Kansas

WELL NAME: #1 COPELAND
LOCATION: SW NW SE
Sec 12-25S-14W
Stafford County, Kansas

CONTRACTOR: **K & E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: May 7th, 1959
COMPLETED: May 15th, 1959

CASING RECORD: 8-5/8" @ 285' (225 sx)

ELEVATION: 1962' KB

ROTARY TOTAL DEPTH: 3975'

PRODUCTION: D&A

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Sand	150
Shale	175
Shale & Shells	285
Shale	850
Anhydrite	870
Shale	1405
Shale & Shells	1565
Salt & Shale	1725
Lime & Shale	2060
Lime	2400
Lime & Shale	2650
Shale & Lime	2840
Shale	2955
Lime & Shale	3240
Shale & Lime	3355
Lime	3595
Shale	3656
Lime	3975

R.T.D.

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1959
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, Dale Silcott, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Dale Silcott
Dale Silcott

Subscribed and sworn to before me this 18th day of May 19 59

Patricia M. Edwards
Patricia M. Edwards, Notary Public.

My Commission expires: August 11th, 1962.

PLUGGING

FILE SEC. 12 T 25 R 14W

BOOK PAGE 39 LINE 26

