


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec. 19 Twp 25S Rge. 11W (E) (W)
 Location as "NE/CNW/SW" or footage from lines C NE NE
 Lease Owner Sierra Petroleum Co., Inc.
 Lease Name Grunder Well No. 1
 Office Address Box 232 Russell, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Oil
 Date well completed 19____
 Application for plugging filed 19____
 Application for plugging approved 19____
 Plugging commenced November 6, 1962 19____
 Plugging completed November 8, 1962 19____
 Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4310 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	298	none
				5 1/2	none	2139

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cleaned out cellar, measured T.D. and sanded to 3750'. Dumped 5 sx. cement and rigged up jacks. Shot @ 3230' and worked pipe.

Shot @ 3130' and worked pipe. Shot at intervals from 3130' to 2120'. Pulled pipe.

Plugged well @ 240' and built 10 ft. rock bridge @ 230'. Dumped 20 sacks cement and mudded to 40'. Capped well with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 1 1962

CONSERVATION DIVISION
Wichita, Kansas

11-13-62

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Forbes Casing Pulling, Inc.
 Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
 J. O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

J. O. Forbes
 Box 221 Great Bend, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 1962

My commission expires July 23, 1966

Carolyn Heaven
 Notary Public.

SIERRA PETROLEUM CO., INC. - Operator

GRUNDER #1
C NE NE - 100' North
Sec. 19-25S-14W
Stafford County, Kansas

T. D.: 4310'
Elev.: 1889' K.B.

Commenced: 10-23-61
Completed: 11-4-61

Casing:

8-5/8" Set at 298'
5-1/2" Set at 4308'

Cement:

with 225 sx. cement
with 125 sx. cement

FORMATION

DEPTH

Sand	190
Shale & Shells	265
Shale & Red Bed	298
Shale	306
Red Bed	918
Anhydrite	931
Shale, Shells & Salt	1700
Shale & Shells	1802
Lime & Shale	2999
Lime	3050
Lime & Shale	3160
Lime	3405
Lime & Shale	3490
Lime	4174
Mississippi	4215
Lime	4282
Viola	4310

RECEIVED
STATE CORPORATION COMMISSION

NOV 6 1962

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and
correct to the best of my knowledge.

C. T. Honsaker
Drilling Superintendent

Subscribed and sworn to before me this 5th day of November,
1962.

LeRoy Dutz
Notary Public

My commission expires: 10-17-63