


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 19 Twp. 25 Rge. 14 (E) (W) X
Location as "NE/CNW/SW" or footage from lines S¹/₄ NW NE
Lease Owner Western Petroleum Company, Inc.
Lease Name Grunder Well No. 1
Office Address 925 Patton Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 1-28-64 19
Application for plugging approved 1-29-64 19
Plugging commenced 2-3-64 19
Plugging completed 2-7-64 19
Reason for abandonment of well or producing formation Dry
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Depth to top Bottom Total Depth of Well 1259 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	253	None
				5 1/2	None	3053

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rigged up. Cleaning out cellar. Measured T. D. Sanded to 1170' with 5 sacks of cement.

Shot well at 3500'. Working pipe. Shot at 3414'. Working pipe. Shot at 3322'. Working pipe.

Shot pipe at 3218'. Working pipe. Shot pipe at 3128'. Working pipe. Shot pipe at 3030'. Pulling pipe.

Pulling pipe.

Plugging well with 15 sacks of mud and 80 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 12 1964

2-12-64
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of February, 1964

My commission expires May 27, 1964

Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


Company. HINKLE OIL CO.
Farm. Grunder

No. 1

SEC. 19 T. 25 R. 14W
O NW NE

Total Depth. 4259'
Comm. 3-4-63 Comp. 3-15-63
Shot or Treated.
Contractor. Red Tiger Drilling Co.
Issued. 6-1-63

County Stafford
KANSAS



CASINO:

Elevation. 1990' RB

8 5/8" 253' cem w/280 sx.

Production. Dry

Figures indicate Bottom of Formations.

sod & sand	195
shale	255
red bed	265
Anhydrite & shells	285
shale shells & redbed	925
Anhydrite	965
shale & shells	1612
shale	1800
shale w/lime	3205
lime	3222
lime & shale	3375
lime	4170
lime & chert	4210
lime	4215
lime shale & chert	4241
lime	4259 RTD
Total Depth	

TOPS: SAMPLE

Anhydrite	925
Heebner	3584
Brown Lime	3726
Lansing	3753
Mississippi	4152
Kinderhook	4183
Viola	4234

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1964
CONSERVATION DIVISION
Wichita, Kansas