


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Stafford County. Sec. 21 Twp. 25S Rge. 11W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE NW NE

Lease Owner Bankoff Oil Company
Lease Name Wilson #1 Well No. 1
Office Address P. O. Drawer 2479, Tulsa, Oklahoma 74101
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed October 30, 1977 19
Application for plugging filed October 29, 1977 19
Application for plugging approved October 29, 1977 19
Plugging commenced 6:00 AM, October 30, 1977 19
Plugging completed 8:00 AM, October 30, 1977 19
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. T. Owen
Producing formation Depth to top Bottom Total Depth of Well 3700'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	282'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud.
10 sacks cement thru open end of drillpipe
at 500'; 35 sacks at 282' K.B.; solid
bridge at 10', 1 sack hulls, Howco plug, 12 sacks
cement. 3 sacks in rat hole.

11-7-77
NOV 07 1977
KANSAS
DIVISION

(If additional description is necessary, use BACK of this sheet.)

Name of Plugging Contractor STERLING DRILLING COMPANY, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
Bernard Laudermilk (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bernard Laudermilk
STERLING DRILLING COMPANY
Bernard Laudermilk, President
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of October, 19 77

CHARLES HALL—NOTARY PUBLIC
My Commission Expires Jan. 6, 1978

Charles M. Hall
Charles M. Hall, Notary Public.

My commission expires

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- WILSON #1

Located: NE NW NE, Section 21-25S-14W, Stafford County,
Kansas

OWNER: Bankoff Oil Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 24, 1977

COMPLETED: October 30, 1977

TOTAL DEPTH: 3700'

LOG

0 - 200	Sand and Gravel
200 - 285	Red Bed
285 - 640	Shale - Red Bed
640 - 848	Shale
848 - 866	Anhydrite
866 - 1570	Shale
1570 - 2255	Lime and Shale
2255 - 2440	Lime
2440 - 2800	Lime and Shale
2800 - 3700	Lime

CASING RECORD

Ran 7 joints new 20#, 8 5/8" casing,
270.90' set at 282' K.B. with 225 sacks
Common with 2% gel and 3% cc. Plug down
at 2:00 AM, 10-25-77, by Sun.

Plugged.

RECEIVED
STATE COMMISSION

NOV 07 1977

CONSERVATION DIVISION
Wichita, Kansas