


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 21 Twp. 25S Rge. 14W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW NE NW
Lease Owner Alpine Oil & Royalty Co., Inc.
Lease Name Wilson Well No. 1
Office Address 1100 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 31, 1956 19
Application for plugging filed December 31, 1956 19
Application for plugging approved December 31, 1956 19
Plugging commenced December 31, 1956 19
Plugging completed December 31, 1956 19
Reason for abandonment of well or producing formation non-productive

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4170 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	263'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from total depth to 240 feet
1/3rd sack hulls, solid plug and 20 sacks cement
at 240 feet, heavy mud to 35 feet, 1/3rd sack
hulls, solid plug and 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Quaker Drilling Co., Inc.
Address 1100 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul
1100 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of January, 19 57

My commission expires August 10, 1957

Virginia Muddell
Notary Public.

PLUGGING
FILE SEC 21 T 25 R 14W
BOOK PAGE 120 LINE 33 DIVISION
Wichita, Kansas

1-3-57

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: December 12, 1956

Contractor: Quaker Drilling Co., Inc.

Completed: December 31, 1956

Roy Wilson No. 1
SW NE NW Sec. 21-25S-14W
Stafford County, Kansas

Elevation: 1984 K. B.

Production: D & A

Casing Record:

Set 263 feet of 8 5/8 inch casing with 275 sacks pozmix

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>Formation Tops</u>	
Surface Clay and Sand	195	Heebner	3516 -1532
Shale	263	Brown Lime	3663 -1679
Red Bed	490	Lansing	3685 -1701
Shale & Shells	895	Base of Kansas City	3960 -1976
Anhydrite	920	Mississippian	4088 -2104
Red Bed	985	Viola	4142 -2158
Shale and Shells	1625	Rotary Total Depth	4170 -2186
Shale and Lime	3668		
Lime and Shale	4170		

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SW NE NW of Section 21, Township 25 South, Range 14 West, Stafford County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. McCaul
Thomas M. McCaul, President

SUBSCRIBED AND SWORN to before me a Notary Public this 2nd day of January, 1957.

Virginia Mundell
Notary Public

MY COMMISSION EXPIRES:
August 10, 1957

PLUGGING
FILE SEC. 21 T. 25 R. 14W
BOOK PAGE 130 LINE 33

RECEIVED
STATE CORPORATIONS COMMISSION
CONSERVATION DIVISION
Wichita, Kansas