

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pratt County, Sec. 12 Twp. 19 Rge. 14 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE/c NW

Lease Owner The El Dorado Refining Company

Lease Name Davis Well No. 1

Office Address 306 Koch Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 6 1954

Application for plugging filed October 6 1954

Application for plugging approved October 6 1954

Plugging commenced October 6 1954

Plugging completed October 6 1954

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4716 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	360	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud through drill pipe to 300', cemented plug with 20 sacks of cement. Filled hole to within 35' of the surface, set top plug with 10 sacks of cement.

10-14-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company

Address Sterling, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Rollin Mead (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Rollin Mead

Sterling, Kansas (Address)


SUBSCRIBED AND SWORN TO before me this 9th day of October, 1954

My Commission Expires Sept. 17, 1957.

[Signature]

Notary Public.

My commission expires



STERLING DRILLING CO.

STERLING, KANSAS

WELL LOG

-----DAVIS #1

Location: SE/c NW, Section 12-19-14W,
Pratt County, Kansas.

OWNER: The El Dorado Refining Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 9-15-54 (w.r.)
COMPLETED: 10-6-54 (w.r.)

TOTAL DEPTH: 4716'

LOG

0-230	Shale & Sand
230-540	Red Bed
540-1300	Red Bed, Shale & Shells
1300-1785	Shale & Shells
1785-1805	Anhydrite
1805-1960	Shale & Shells
1960-2080	Lime
2080-2185	Shale & Lime
2185-2755	Lime
2755-3285	Shale & Lime
3285-3620	Lime
3620-3710	Shale & Lime
3710-3745	Lime
3745-4035	Shale & Lime
4035-4550	Lime
4550-4555	Viola Lime
4555-4611	Lime
4611-4655	Simpson
4655-4716	Simpson & Shale T. D.

CASING RECORD

Ran 360' of 8-5/8" casing cemented
with 250 sacks bulk cement and 2 sacks
calcium chloride.

PRODUCTION

Plugged and Abandoned.

RECEIVED
REGISTRATION COMMISSION
OCT 11 1954
REGISTRATION DIVISION
Pratt, Kansas

