

KANSAS

10
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued April 14, 1967.

Operator's Full Name Skelly Oil Company

Complete Address P. O. Box 649, McCook, Nebraska 69001

Lease Name I. M. Toland Well No. # 1

Location C S/2 SW NW Sec. 27 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 3920'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Comstock Pipe Pulling, Inc.

Address Stafford, Kansas License No. 490

Operation Completed: Hour 10:00 A.M Day 27th Month June Year 1967

The above well was plugged as follows:

857' of 8 5/8" surface pipe, cement circulated. 3920' of 5 1/2" long string,
cemented with 150 sacks. Plug back T.D. 3890'. Top perforation 3844'. Bottom
of the hole was sanded to 3800', and cemented with 20 sacks, through the
dump bailer. 2202' of 5 1/2" long string was recovered from the hole. Fluid
level in the hole was at 290', bridge plug and rock bridge from 290' to 280',
and cemented with 25 sacks. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 7/3/67
INV. NO. 5514-W