

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202 Well Plugging Authority,
issued April 14, 1967.

7-5-1967
RECEIVED
STATE CORPORATION COMMISSION

JUL 5 1967

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company
Complete Address P. O. Box 649, McCook, Nebraska 69001
Lease Name I. M. Toland Well No. # 2
Location SW SE NW Sec. 27 Twp. 25 Rge. 14 (E) (W)W
County Stafford Total Depth 3942'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Comstock Pipe Pulling, Inc.
Address Stafford, Kansas License No. 490
Operation Completed: Hour 12:15 P.M. Day 4th Month July Year 1967

The above well was plugged as follows:

855' of 8 5/8" surface pipe, cement circulated. 3942' of 5 1/2" long string,
cemented with 60 sacks. Plug back T.D. 3908'. Top perforation 3850'. Bottom
of the hole was sanded to 3800', and cemented with 20 sacks, through the
dump bailer. 3178' of 5 1/2" long string was recovered from the hole. Fluid
level in the hole was at 325', bridge plug and rock bridge from 325' to
305', and cemented with 25 sacks. Hole was filled with mud to 40', rock
bridge from 40' to 30', and cemented with 10 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/5/67INV. NO. 5522-11