

15-185-20572-0000

KANSAS

Form CP-3
Rev. 6-1-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Wayne Kirkman
Complete Address 434 N Market Wichita, KS
Lease Name Wiles Well No. 1
Location SE/NW/SW Sec. 27 Twp. 25s Rge. 14 (E) (W) W
County Stafford Total Depth 2879
Abandoned Oil Well Gas Well X Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Art Lamb Casing Pulling Co
Address 2809 King Hutchinson, KS License No. 440
Operation Completed: Hour 11: AM Day 20 Month 8 Year 1976

The above well was plugged as follows:

236 ft 8 5/8 surface cemented with 200 sacks. 2879 ft 4 1/2 long string
cemented with 300 sacks. Top perf. 2055 ft. Pump plug to 2025 ft,
4 sacks cement with bailer. Pulled 1735 ft 4 1/2. Pump 2 sacks hulls,
10 sacks gel, 100 sacks cement to surface.
Pumped by Allied Cementing Great Bend, KS

STATE CORPORATION COMMISSION
RECEIVED 8-23-1976

AND 23 1976
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

INV. NO.

Signed:

Well Plugging Supervisor

8/23/76

3675-W