

P P

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

APR 1 - 1970

CONSERVATION DIVISION
Wichita, Kansas

4-1-1970

Operator's Full Name Braden-Deem Inc.Complete Address Suite 520 200 East 1st. Wichita, Ks 67202Lease Name A.L.WilesWell No. 1Location NW/NW/SWSec. 27 Twp. 25 Rge. 14 (E) (W) WCounty StaffordTotal Depth 3844-3944'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated Plugging Contractor Forbes Casing Pulling Co.Address Box 221 Great Bend, KsLicense No. 49Operation Completed: Hour 4:00PM Day 30 Month 3 Year 1970

The above well was plugged as follows:

878 ft of 8 5/8 surface pipe cemented with 500 sacks. 3944 ft of
5 1/2 long string cemented with 150 sacks. Top perf 3846 ft. Sand
back to 3835 ft., 5 sacks cement with bailer. Pulled 2670 ft. of
5 1/2. Mud to 250 ft, 10 ft rock bridge, 25 sacks cement. Mud to 40 ft.,
10 ft rock bridge, 10 sacks cement to top of surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M Russell Biberstein
Well Plugging SupervisorDATE 4-1-70INV. NO. 1669-W