

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

STATE RECEIVED  
FORM 30-3  
RECORDATION COMMISSION  
Rev. 6-21-68

FEB 20 1979  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name J. L. Kirkman, Inc.

Complete Address Box 18611, Wichita, Kan. 67207

Lease Name Russell Well No. 1

Location C-1/2-NE-SE- Sec 27 Twp. 25 Rge. 14 (E) (W) X

County Stafford Total Depth 3240

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Falso Casing Pulling

Address Box 176 Chase, Kans. 67524 License No. 683

Operation Completed: Hour 2:45 pm Day 17 Month 2 Year 1979

The above well was plugged as follows:

295' - 8 5/8" Casing w/ 250 sac Cement - 4 1/2" Casing set @ 2192' w/  
150 sac Cement - plug back to 2161' Prof @ 2003' - 07' - 2 1/2" -  
mixed & pumped 35 sac Cement in 4 1/2" casing & base  
plug & pumped plug to 1700' - pull 1668' 4 1/2" casing -  
skin mixed & pumped 5 sac Buller 16 sac gel - release plug -  
mixed & pumped 100 sac 50/50 porous Cement w/ 29 gal - 29 cc  
in 8 5/8" Casing to top of Casing - shut in w/ 0" pressure

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 2-21-79

INV. NO. 9149. w