

RE

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 108-12 County: STAFFORD

Location: NW-NW-SW Sec. 28 Twp. 25 Rge. 14 (E) (W)

Name of Field: _____ Total Depth: 4070'

I have this date completed supervision of plugging of:

Lease Name: NELLIE WATERS Well No. 1-A

Operator's Full Name: ALPINE OIL & ROYALTY CO. INC

Complete Address: 1100 BITTING BLDG WICHITA, KANS

Plugging Contractor: R & D CASING PULLING CO

Address: ELLINWOOD, KANS License No. 236

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 7:00 PM Day 17 Month JUNE Year 1958

The above well was plugged as follows:

8 7/8 - 286' w/250 SX C. TOP PERFORATION 3906'
SANDED PIPE BACK TO 3890' w/5 SX CMT PLUG -
SHOT PIPE - FILLED HOLE w/MUD TO 250' - SET
10' ROCK BRIDGE w/20 SX CMT PLUG - MUDDER TO
40' - w/10' ROCK BRIDGE - 10 SX CMT CAP TO
BOTTOM OF CELLAR

Signed: Frank Bragg
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 28 T. 25 R. 14W
BOOK PAGE 108 LINE 12