

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-047-20,457-600 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Rupe Oil Company, Inc. KCC LICENSE # 5047 998
(owner/company name) (operator's)

ADDRESS P.O. Box 783010 CITY Wichita,

STATE Kansas ZIP CODE 67278 CONTACT PHONE # (316) 262-3748

LEASE Desemo WELL# 1 SEC. 9 T. 26S R. 18W (East/West)

SE -NW -SW SPOT LOCATION/QQQQ COUNTY Edwards

1650 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM E/(W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8" SET AT 361' CEMENTED WITH 300 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 4746' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs: 4673-75 4660-65

ELEVATION 2181/2190 T.D. 4730' PBDT 4679' ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING ACCORDING TO THE RULES AND REGULATIONS OF THE STATE OF KANSAS.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED?

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Cindi Curtis PHONE# (316) 262-3748

ADDRESS P.O. Box 783010 City/State Wichita, Ks. 67278

PLUGGING CONTRACTOR Mike's Testing & Salvage Inc. KCC LICENSE # 31529
(company name) (contractor's)

ADDRESS P.O. Box 467 Chase, Kansas 67524 PHONE # () (316) 938-2943

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) ASAP

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 12-23-97 AUTHORIZED OPERATOR/AGENT: Mike Salvo
(signature)



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

December 30, 1997

Rupe Oil Company Inc
P O Box 783010
Wichita KS 67278

Desemo #1
API 15-047-20,457-~~0000~~
1650 FSL 990 FWL
Sec. 9-26S-18W
Edwards County

Dear Cindi Curtis,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760

KANSAS DRILLERS LOG

API No. 15 — 047 — 20,457-0000
 County Number

S. 9 T. 26 R. 18 W

Loc. SE NW SW

County Edwards

Operator

Rupe Oil Co., Inc.

Address

P. O. Box 2273 Wichita, Kansas 67201

Well No.

#1

Lease Name

Desemo

Footage Location

1650 feet from (S) (S) line 990 feet from (E) (W) line

Principal Contractor

B & N Drilling Company

Geologist

Spud Date

December 6, 1978

Total Depth

4730'

P.B.T.D.

4679'


Date Completed

February 13, 1979

Gas Purchaser

Kansas-Nebraska Natural Gas. Co. DF KB 2190'

640 Acres
N



Locate well correctly

Elev.: Gr. 2181'

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		361'	Class 'A'	300	2% Gel, 3% Calcium Chloride
Production	7 7/8"	4 1/2"		4746'	50-50 Pozmix	150	10% Salt .75 CFF

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	DP	4673' - 75'
			1	DP	4660' - 65'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1000 gals. 15% MCA w/ 100,000 SCF N ₂ , re-acidized w/	4660'-65'
72 bbls. MOD 202 Acid w/ 100,000 SCF N ₂	4673'-75'

INITIAL PRODUCTION

Date of first production <u>September 30, 1979</u>		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
		<u>200</u> bbls.	<u>3</u> MCF		<u>CFPB</u>
Disposition of gas (vented, used on lease or sold)			Producing interval (s) <u>4660'-65' & 4673'-75'</u>		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, a completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.