

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-151-21993-00-00 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Vincent Oil Corporation OPERATOR'S LICENSE NO. 5004

ADDRESS 100 N. Main, Suite 500, Wichita, KS 67202 PHONE # (316) 262-3573

LEASE (FARM) Moss WELL NO. 1 WELL LOCATION App. NE SE SW COUNTY Pratt

SEC. 10 TWP. 29S RGE. 14 (X) or (W) TOTAL DEPTH 4675 PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 380.18 CEMENTED WITH 225 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Plug at 900' w/50 sx; plug at 400' w/40' sx; plug at 40' w/10
sx; rathole 15' sx; mousehole 10 sx; water well 10 sx: 135 sacks cement, 60/40 pozmix w/6%
gel

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? no
(If not explain.) sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 1:00 a.m. 5-30-90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harvey Moore PHONE # (316) 995-4955

ADDRESS Box 163, Belpre, KS 67519 *RECEIVED STATE CORPORATION COMMISSION 06-21-90*

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED:

Jack K. Wharton
(Operator or Agent) Jack K. Wharton