



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-047-10063-00-01

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. F. L. Copeland of Western Petroleum Co. Inchas this date requested permission to plug the following described well:

Mr. Copeland guarantees payment of the plugging fee.

Operator's full Name: Western Petroleum Co., Inc.

Complete Address: Box 65, Great Bend, Kansas

Lease Name: Newsom Well No. # 1

Location: C SW NE Sec. 11 Twp. 26 Rge. 18 (E) (W) W

County Edwards Total Depth 3365 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Copeland was instructed to plug the well as follows:

283' of 8 5/8" surface pipe, cement circulated with 200 sacks.
Fill hole with drilling mud to 275', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent