



JOHN ANDERSON, Jr. Governor
WILLIAM L MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-047-30000-0000

RECEIVED
STATE CORPORATION COMMISSION

FEB 4 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Fred Glick of Skelly Oil Company has this

date requested permission to plug the following described well:

Mr. Glick guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name: Belcher "A" Well No. # 1

Location: C SE NW Sec. 17 Twp. 26 Rge. 18 (E) (W) W

County Edwards Total Depth 3422 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Glick was instructed to plug the well as follows:

315' of 8 5/8" surface pipe, cement circulated with 200 sacks.

Fill hole with drilling mud to 300', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with

2 sacks.

Very truly yours,

Archie Elving

Conservation Division Agent