

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

RECEIVED  
STATE CORPORATION COMMISSION  
FORM CP-2  
DEC 8 1981  
CONSERVATION DIVISION  
Wichita, Kansas

State Corporation Commission  
CONSERVATION DIVISION  
(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

28 September 1981

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Albert Hnuch of Kelso Casing Pulling has this date requested permission to plug the following described well:

Operator's Full Name: Edwards Oil Inc.

Complete Address: 1215 E 30th Box 206 Hutchinson Kansas 67501

Lease Name: Russell Well No. 1

Location: C-5 1/2 - NE SW Sec. 26 Twp. 25S Rge. 16W (E) (W)

County: Edwards Total Depth: 4423'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: Well was completed but never produced

Mr. Hnuch was instructed to plug the well as follows:

There is 472' of 5 1/8" surface casing cemented circulated with 400 lbs of cement. The cement was composed with 4% Jell + 3% C.C. There is 4418' of 4 1/2" production pipe cemented with 175 lbs of cement 50/50 pause 0/8% salt 3/4 C.F.R. 1st plug after squeezing bottom hole sand to 4350' and 4 lbs of cement 2nd plug pumped in 4 lbs of bull 25 lbs of Jell + 150 lbs of cement. The cement used was 50/50 pause 4% Jell 3% C.C. There was 2600' of production pipe recovered.

Very truly yours,

Paul Luttich  
Conservation Division Agent

(over)

Mr. Keith Smith of Edwards Oil had Kelsee move off of  
hole. October 1, 1981. I called Mr. Smith October 2-1981  
to find out when he was going to finish the plugging,  
I called him again on 11-19-81 & again 11-30-81 to get it  
plugged. He always put me off a few days. Halliburton  
Co. finally completed the plugging in December. Mr. Murak  
told me there was no gas pressure shut in the day they  
went to location, shut in pressure after pumping down  
plug was 100 lbs.

Paul Luthi