

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 4 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

March 29, 1968.

Dear Sir:

Mr. Ben Thompson of Pipe Pullers Inc. has this

date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling Co.

Complete Address: 815 Wichita Plaza, Wichita, Kansas.

Lease Name: Wilson Well No. #5

Location: C-NE-SE Sec. 26 Twp. 25S Rge. 16 (E)(W) W

County: Edwards Total Depth 4460' Oil Well Abd.

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Thompson was instructed to plug the well as follows:

342 ft. of 8 5/8" surface pipe circulated with 275 sacks
cement. Top perforation at 4402 ft. Sand to 4390 ft. & 5 sacks
cement. Mud to 300 ft., 10 ft. rock bridge & 5 sacks cement,
as overnite bridge, hole bailed down & 20 sacks cement. Mud
to 40 ft. 10 ft. rock bridge & 10 sacks cement to surface.
3322 ft. of 5 1/2" pipe recovered. Very truly yours,

Thomas J. Gustus
Conservation Division Agent