

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

NOV 6 1977

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Richards of Sage Drlg. Co. has this date requested permission to plug the following described well:

Mr. Richards guarantees payment of the plugging fee.

Operator's full Name: O.F.S. Inc

Complete Address: 630 Founders Life Tower Oklahoma City, OK

Lease Name: F.W. Lamb Well No. 5

Location: C SE Sec. 25 Twp. 25s Rge. 16 (E)(W) W

County: Edwards Total Depth 4375 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Richards was instructed to plug the well as follows:

368 ft 8 5/8 surface pipe cemented with 250 sacks. Pump

40 sacks cement to 600 ft. 2nd plug at 300 ft, with 35

sacks cement. Mud to 40 ft, plug, 1/2 sack hulls, 15 sacks

cement to surface. 2 sacks cement in rat hole.

Pumped by Globe Cementing Co. Great Bend, Ks

Very truly yours,

Conservation Division Agent