



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Willard French of The C. L. Morris Oil Corp. has this date requested permission to plug the following described well:

RECEIVED
STATE CORPORATION COMMISSION
12-1-81
DEC - 1 1981

Operator's Full Name: The C. L. Morris Oil Corp

Complete Address: P.O. Box 204, 200 Hardage Center, 100 S. Main

CONSERVATION DIVISION
WICHITA, KANSAS

Lease Name: Griggell Shepard Well No. 1

Location: 140' NW of C. 5 E Sec. 23 Twp. 25 S Rge. 16 W (E) (W)

County: Edwards Total Depth: 4450'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: Production pipe runs tested but never produced

Mr. French was instructed to plug the well as follows:

There is 370' of 8 5/8" surface casing cement circulated. There is 4450' of 4 1/2" production pipe cemented to 3800'. There is a plug at 4357'. The perforations are at 4351' to 4354'. 1st plug sanded off bottom with 4 lbs of cement. 2nd plug 5 lbs Jell, 5 lbs shells 5 lbs Jell then 50 lbs of cement released rubber plug and put 50 lbs on top of it. Plugging accomplished by Halliburton Co. Pratt Ks

Very truly yours,

Paul Luthie

Conservation Division Agent

There were 2020' of production pipe recovered