

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 12-18-62
 DEC 18 1962

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Kent Eby of Mack Drilling Co. has this

date requested permission to plug the following described well:

Mr. Kent Eby guarantees payment of the plugging fee.Operator's full Name: Mack Drilling Co.Complete Address: R.R.#1 Kingman, KansasLease Name: Torline "B" Well No. 7Location: C NW SE Sec. 33 Twp. 25 Rge. (E) (W) 21County Ford Total Depth 4803' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Kent Eby was instructed to plug the well as follows:8 5/8" 284' Circulated w/cement. 4 1/2" 4796' Cemented.Sand 4803' to 4775' 5 sax.cement 4775' to 4750'Mud 4750' to 275' Plug and 35 sax.cement 275' to 175'Mud 175' to 50' Rock bridge 50' to 40'15. sax.cement 40' to Surface.

Very truly yours,

F. Hugh Scott
 Conservation Division Agent