

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Adams of H & H Supply Co. has this

date requested permission to plug the following described well:

Mr. Adams guarantees payment of the plugging fee.

Operator's full Name: H & H Supply Company

Complete Address: Box 95226, Oklahoma City, Oklahoma

Lease Name: Troy Mahoney-Butler Well No. 5

Location: NE NW Sec. 33 Twp. 25 Rge. 21 (X) (W)

County Ford Total Depth 4835' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Adams was instructed to plug the well as follows:

8 5/8" to 192' circulated w/ cement. 4 1/2" to 4327' cemented.

Top perforations 4229' Plug bottom w/ 20 sacks cement.

Top of cement 4000' Mud 4000' to 700'

Spot 30 sacks cement 700' to 600' Mud 600' to 190'

Spot 30 sacks cement 190' to 100' Mud 100' to 40'

Plug, Halls & 10 sacks cement 40' to 0'

Very truly yours,

Edward Jones
Conservation Division Agent